

OIL & GAS

World leaders in valve integrity

Innovating for tomorrow



TECHNICAL DATA SHEET

Product Code: D0905
Quality Standards:
ISO 9001:2015
ISO 14001: 2015
Issue Date—February 2017
Revision—04

ClareTech Valve Sealant 701

Heavy-duty valve sealant.
NLGI 2

Introduction

API 6A gate valves are designed to achieve a metal-to-metal seal between the gate and seat. In some cases, the seal surfaces can be damaged, either because of insufficient preventative maintenance, poor choice of service lubricant, arduous operating conditions, or a combination of all.

In such cases, ClareTech Valve Sealant 701 may be injected into the valve cavity to assist in achieving a seal across the gate or seat surfaces. The ability of any sealant to provide a seal that will sustain full wellhead pressure depends upon its performance and the specific condition of the valve components. ClareTech Valve Sealant 701 is field-proven as highly effective.

Description

ClareTech Valve Sealant 701 is a specially formulated heavy-duty valve sealant. In full-scale valve testing, it has been proven to seal a severely leaking valve. ClareTech Valve Sealant 701 is fully resistant to all types of produced hydrocarbons, and also to high levels of H₂S and CO₂.

ClareTech Valve Sealant 701's physical texture and high metal adhesion promotes extended cavity retention. ClareTech Valve Sealant 701 also has enhanced lubricating properties to protect the sealing surfaces during further functioning of the valve under high differential pressures.

ClareTech Valve Sealant 701 is fully compatible with our ClareTech Valve Lubricant 601 range.

Applications

ClareTech Valve Sealant 701 should be used in gate valves with moderate to severe leaks where the use of ClareTech Valve Lubricant 601 has not been successful in assisting the valve to hold pressure. ClareTech Valve Sealant 701 may be injected into plug and ball valves in an attempt to assist with emergency sealing, and it is also able to be pumped by high pressure pumps.

Testing

ClareTech Valve Sealant 701 has been tested in an API 6A gate valve with a severely damaged seat component deliberately cut to a depth of 1.5mm. ClareTech Valve Sealant 701 was able to hold 5,000 psi, which is the pressure limit of a valve.

Note – A leading valve sealant was tested alongside. ClareTech Valve Sealant 701, in the same test the valve sealant would not even assist the valve to pressurise. A test report is available on request.

Typical Characteristics

Appearance	Visual	Adhesive
Colour	Visual	Black/Grey
Thickener		Inorganic (non-soap)
Temperature Range		0°F to 350°F
Unworked Penetration	IP 50	265-295
Drop Point	IP 396	Non-melting
4-Ball Weld Load	IP 239	>620kg

Base Oil Characteristics

Type		Synthetic
------	--	-----------

Important Note

The injection of a sealant is a temporary measure. The valve is leaking due to physical damage to the sealing surfaces, the valve or its components should be changed out at the earliest opportunity. The sealant may be employed to assist in regaining integrity, so that well intervention operations can be carried out in a cost-effective manner.

ClareTech Valve Sealant 701 can be pumped by high pressure-pumps. Please contact RS Clare for pump specification advice.

*It is the sole decision of the operator if a sealant is employed to assist to restore or maintain the integrity of a valve as a well barrier. *Prior to injecting 701, the operator should identify the exact make, model and pressure rating of the gate valve, and confirm the arrangement of the sealant injection fitting(s) in the valve's bonnet. If a buried check valve is present, please utilise 701-L.*

OIL & GAS

World leaders in valve integrity


Innovating for tomorrow



TECHNICAL DATA SHEET

Product Code: D0905
Quality Standards:
ISO 9001:2015
ISO 14001: 2015
Issue Date—February 2017
Revision—04

Secondary, “Buried” Injection Check Valve Fitting



*It is the sole decision of the operator if a sealant is employed to assist to restore or maintain the integrity of a valve as a well barrier. *Prior to injecting 701, the operator should identify the exact make, model and pressure rating of the gate valve, and confirm the arrangement of the sealant injection fitting(s) in the valve's bonnet. If a buried check valve is present, please utilise 701-L.*